

KEY - HARD LANDSCAPING SURFACES

HARD LANDSCAPING - ROADWAY SURFACE
ROADWAY / KERBING TO BE INSTALLED TO ENGINEER'S DETAIL / DESIGN.

HARD LANDSCAPING - ROADWAY SURFACE - RAISED TABLE
ROADWAY / KERBING TO BE INSTALLED TO ENGINEER'S DETAIL / DESIGN.

HARD LANDSCAPING - BRUSHED CONCRETE
TO BE INSTALLED TO ENGINEER'S DETAIL / DESIGN.

HARD LANDSCAPING - KILSARAN 'CLIMAPAVE NEWGRANGE' BLOCK
SILVER GRANITE EDGING / CHARCOAL INFILL COLOURS IN 3 SIZE MIX AND LAID IN **RANDOM STRETCHER BOND** PATTERN - OR SIMILAR AND APPROVED. SUB-BASE INSTALLED TO ENGINEERS / MANUFACTURERS DETAIL / DESIGN.

HARD LANDSCAPING - KILSARAN 'SHELBOURNE' FLAG
SILVER GRANITE COLOUR IN 600 X 300 X 50 MM UNITS AND LAID IN **STRETCHER BOND** PATTERN TO REAR GARDENS OF UNITS - OR SIMILAR AND APPROVED. CHARCOAL COLOUR TO BE USED IN MIX WITH SILVER GRANITE COLOUR TO AMENITY SPACE PAVING. SUB-BASE INSTALLED TO ENGINEERS / MANUFACTURERS DETAIL / DESIGN.

HARD LANDSCAPING - SAFETY SURFACE GRASS MATTING
'RUBBA GRASS' OR SIMILAR AND APPROVED EQUIVALENT GRASS MATTING PRODUCT AS SPECIFIED / SUPPLIED BY THE PLAY EQUIPMENT PROVIDER. CERTIFICATED TO EN 1177. SUB-BASE INSTALLED TO MANUFACTURERS / ENGINEERS DETAIL / DESIGN.

HARD LANDSCAPING - BUFFED TONED TARMAC (OR SIMILAR AND APPROVED SURFACE)
NATURAL BUFF TONED TARMAC INSTALLED TO ENGINEERS / MANUFACTURERS DETAIL / DESIGN. EDGED WITH CONCRETE PIN KERBING. FINISH TO BE AGREED WITH CLIENT PRIOR TO INSTALLATION .IN AREAS OF TREE PROTECTION, A 'NO-DIG' METHODOLOGY SHOULD BE USED. PLEASE REFER TO THE ARBORICULTURAL REPORT FOR FURTHER INFORMATION.

HARD LANDSCAPING - CONCRETE ROAD KERBING
TO BE INSTALLED TO ENGINEER'S DETAIL / DESIGN.

HARD LANDSCAPING - KERBING - PRECAST CONCRETE PIN KERB
FLAT TOP CONCRETE PIN KERB TO EDGE ALL TARMAC SURFACES. PIN KERB TO BE BE HAUNCHED WHERE PAVING MEETS A SOFT LANDSCAPING TREATMENT.

HARD LANDSCAPING - TACTILE PAVING
TO BE INSTALLED TO ENGINEER'S DETAIL / DESIGN.

KEY - HARD LANDSCAPING BOUNDARIES

BOUNDARY TYPE 5
1.2M HIGH ESTATE RAILING.
SINGLE LEAF SELF-CLOSING ESTATE RAIL GATE TO MATCH.

KEY - HARD LANDSCAPING ELEMENTS

MMCITE – EMAU SOLO (EMS456 / EMS457)
CENTRAL-LEG PARK BENCH WITH BACKREST AND ARMRESTS. ERGONOMICALLY ADAPTED FOR ELDERLY USERS; CAST ALUMINIUM FRAME WITH SEAT AND BACKREST IN STAINLESS STEEL RODS.

EXTERNAL MULTI-USE GAMES TABLE
HIGH-QUALITY, DURABLE OUTDOOR TABLE FOR RECREATIONAL USE (E.G. TABLE TENNIS, SOCIAL SEATING OR SIMILAR), OR SIMILAR APPROVED, SUITABLE FOR PERMANENT EXTERNAL INSTALLATION.

PLAY EQUIPMENT ELEMENT 1
KOMPAN - CRAWLING PYRAMID - PRODUCT NUMBER NRO826 - ROBINIA. PLEASE REFER TO THE ACCOMPANYING LANDSCAPE DESIGN REPORT FOR FURTHER DETAILS & SPECIFICATIONS.

PLAY EQUIPMENT ELEMENT 2
KOMPAN - TRIPLE BALANCE BEAM - PRODUCT NUMBER NRO804 - ROBINIA. PLEASE REFER TO THE ACCOMPANYING LANDSCAPE DESIGN REPORT FOR FURTHER DETAILS & SPECIFICATIONS.

PLAY EQUIPMENT ELEMENT 3
KOMPAN - STILTS - PRODUCT NUMBER NRO806 - ROBINIA. PLEASE REFER TO THE ACCOMPANYING LANDSCAPE DESIGN REPORT FOR FURTHER DETAILS & SPECIFICATIONS.

PLAY EQUIPMENT ELEMENT 4
KOMPAN - TRIPLE SOMERSAULT - PRODUCT NUMBER NRO809 - ROBINIA. PLEASE REFER TO THE ACCOMPANYING LANDSCAPE DESIGN REPORT FOR FURTHER DETAILS & SPECIFICATIONS.

PLAY EQUIPMENT ELEMENT 6
KOMPAN - EMBANKMENT SLIDE 2 - PRODUCT NUMBER NRO308 - ROBINIA. PLEASE REFER TO THE ACCOMPANYING LANDSCAPE DESIGN REPORT FOR FURTHER DETAILS & SPECIFICATIONS.

NATURAL PLAY ELEMENT 1
NATURAL PLAY ELEMENTS, SUCH AS ROCKS AND LOGS, ARE TO BE SUPPLIED BY PLAYDALE OR A SIMILAR PLAY AREA PROVIDER TO ENSURE THEY ARE SUITABLE FOR PLAYGROUND USE AND CAN OBTAIN ROSPA APPROVAL. THESE ELEMENTS SHOULD BE POSITIONED TO FACILITATE THE MAINTENANCE OF SURROUNDING AREAS.

NATURAL PLAY ELEMENT 2
STONE BOULDERS - LANDSCAPE FEATURE BOULDERS TO BE INTEGRATED THROUGHOUT LANDSCAPE. BOULDERS TO BE LOCATED TO ENSURE EASE OF MAINTENANCE OF SURROUNDING AREAS.

PUBLIC LIGHTING STANDARDS
TO BE INSTALLED TO JAK ENGINEERING'S DETAIL / DESIGN.



SITE INDICATION PLAN @1:4000

DETENTION BASIN AREAS
SWALES / ATTENUATION AREAS TO HAVE SLOPES OF NO GREATER THAN 1:5 TO ENSURE EASE OF MAINTENANCE. PLEASE REFER TO ENGINEER'S DETAILS FOR SPECIFICATIONS RELATING TO ATTENUATION AND DRAINAGE DETAILS.

KEY - SOFT LANDSCAPING

PLEASE NOTE – THE PROPOSED DEVELOPMENT WILL REQUIRE THE REMOVAL OF A NUMBER OF INDIVIDUALLY RECORDED TREES AS WELL AS SOME AREAS OF HEDGEROW. THE REMOVAL OF TREES AND HEDGEROWS HAS BEEN REVIEWED BY THE MULTI-DISCIPLINARY DESIGN TEAM, INCLUDING THE ARBORICULTURAL CONSULTANT, TO ENSURE THAT THOSE TREES AND HEDGEROWS IDENTIFIED FOR RETENTION ARE VIABLE AND REALISTIC.

THIS LANDSCAPE SCHEME PROPOSES THE PLANTING OF 601 NEW TREES, SIGNIFICANTLY EXCEEDING THE NUMBER OF TREES PROPOSED FOR REMOVAL. THE PROPOSED NEW TREES ARE APPROPRIATE AND SUSTAINABLE WITHIN THE LANDSCAPE SETTING AND WILL PROVIDE A HIGH BIODIVERSITY VALUE THROUGH THE USE OF A WIDE VARIETY OF SPECIES. LARGE AREAS OF NATIVE HEDGEROW MIX PLANTING ARE ALSO PROPOSED TO MITIGATE THE LOSS OF EXISTING HEDGEROW. SUPPLEMENT RETAINED HEDGEROWS, AND ESTABLISH NEW HEDGEROWS WHERE APPROPRIATE.

EXISTING HEDGEROW - TO BE RETAINED / OUTSIDE DEVELOPMENT AREA.
PLEASE REFER TO ARBORIST'S REPORT FOR FURTHER INFORMATION.

PROPOSED STREET TREES
T1 - ACS - ACER CAMP. 'STREETWISE' 12-14 CM GTH, 3-4M HT
T2 - CC - CORYLUS COLURNA 10-12CM GTH, 3-4M HT,
T3 - CB - CARPINUS BETULUS 12-14CM GTH, 3-4M HT,
T4 - UL - ULMUS 'LOBEL' 12-14 CM GTH, 3-4M HT

PROPOSED PARKLAND TREES
LARGE TREES
T5 - AG - ALNUS GLUTINOSA 12-14 CM GTH, 3-4M HT,
T6 - QP - QUERCUS PETREA 16-18CM GTH, 4-6M HT
T7 - FS - FAGUS SYLVATICA 12-14 CM GTH, 3-4M HT,
T8 - PS - PINUS SYLVESTRIS 12-14 CM GTH, FEATHERED,
T9 - TC - TILIA CORDATA 16-18CM GTH, 4-6M HT,
T10 - MG - METASEQUOIA GLYPTOSTROBOIDES 14-16 CM GTH, 4-6M HT

SMALL - MEDIUM TREES
T11 - BP - BETULA PENDULA 10-12CM GTH, 3-3M HT,
T12 - MSE - MALUS SYLVESTRIS (EVEREST) - 10-12CM GTH, 2-3M HT,
T13 - PA - PRUNUS AVIUM 14-16CM, 3-4M HT,
T14 - AC - ACER CAMPESTRE 10-12CM GTH, 2-3M HT
T15 - AMC - AMELANCHIER CANADENSIS, MULTISTEM 1-2M HT
T16 - LS - LIQUIDAMBAR STYRACIFLUA 12-14 CM GTH, 3-4M HT

PROPOSED FEATURE TREES
T17 - PS - PINUS SYLVESTRIS, 16-18CM GTH, 4-5M HT
T18 - QR - QUERCUS ROBUR, 16-18CM GTH, 4-6M HT
T19 - PN - PINUS NIGRA, 16-18CM GTH, 4-5M HT
T20 - BP - BETULA PENDULA, 16-18CM GTH, 4-6M HT

THE TREE PLANTING MIX FOLLOWS THE SANTAMOUR RULE (30:20:10) TO PROMOTE SPECIES DIVERSITY, REDUCING RISKS FROM PESTS, DISEASES, AND CLIMATE STRESS. ALL TREES SHALL BE STAKED OR GUYED APPROPRIATELY TO ENSURE STABILITY AND PROPER GROWTH. ALL QUERCUS SPECIES TO BE OF IRISH STOCK.

AMENITY GRASS - PUBLIC SPACES
HARDWEARING SEED MIX TO BE USED.

GRASS AND BLUB MIX
HARDWEARING SEED MIX TO BE USED.
PLEASE REFER TO SOFT LANDSCAPE PLAN AND PLANTING SCHEDULE (595-PD-03.1) FOR FURTHER DETAILS.

PROPOSED GRASS SURFACE WATER SWALES
SWALES TO BE FORMED WITH GRATED OUTLETS. PLEASE REFER TO ENGINEERING DRAWINGS / THE ACCOMPANYING DESIGN REPORT FURTHER DETAILS.

NATIVE HEDGEROW MIX
PLEASE REFER TO SOFT LANDSCAPE PLAN AND PLANTING SCHEDULE (595-PD-03.1) FOR FURTHER DETAILS.

HEDGE 1 - *FAGUS SYLVATICA*
PLEASE REFER TO SOFT LANDSCAPE PLAN AND PLANTING SCHEDULE (595-PD-03.1) FOR FURTHER DETAILS.

A MINIMUM 7M CLEARANCE MUST BE MAINTAINED BETWEEN ALL LAMP STANDARDS AND PROPOSED STREET TREES. LAMP STANDARDS TO BE LOCATED ON HARDSTANDING ONLY.

AVOID LOCATING TREE PLANTING WITHIN 2.5M OF UNDERGROUND SERVICES WHEREVER POSSIBLE.

WHERE POSSIBLE AND APPROPRIATE ENSURE A MINIMUM 2M SETBACK FROM BOUNDARY WALLS, PATHWAYS, AND KERBING.

WHERE TREE PLANTING WITHIN 2.5M OF UNDERGROUND SERVICES IS UNAVOIDABLE (E.G., STREET TREES), AN APPROPRIATE ROOT BARRIER SYSTEM MUST BE INSTALLED TO PREVENT ROOT INGRESS.

DO NOT SCALE FROM THIS DRAWING, WORK ONLY FROM FIGURED DIMENSIONS.
ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE NOTED.
ALL ERRORS AND OMISSIONS ARE TO BE REPORTED TO LANDSCAPE ARCHITECT.

REV:	DATE:	REFERENCE:	BY:	REV:	DATE:	REFERENCE:	BY:
A	2026-04-15	ISSUED FOR SUBMISSION	CC				

MURPHY + SHEANON
Contact: office@murphysheanon.ie
Tel: +353 1 5390540
Address: Ground Floor, Mounttown House, Lower Mounttown Road, Glenageary, Co.Dublin

CLIENT: BALLYMORE DEVELOPMENTS LIMITED.	DRAWING NUMBER: 25-595-PD-05
	PROJECT NUMBER: 25-595
PROJECT: NAAS RACECOURSE	PROJECT STATUS: PLANNING / REVISION: REV. A
	DATE: APRIL 2026
TITLE: LANDSCAPE FOCUS AREA 1	SCALE: 1:200 / A1
	DRAWN BY: RB / CHECKED BY: KR/CS
CAD FILE REFERENCE: h:\shared drives\murphy sheanon office\m+s_office\jobs\2503595 - ballymore - naas racecourse\01 m+s\2. planning\25-595-pd v2026.04.14.dwg	